

1.0 GENERAL

1.1 Scope

- 1.1.1 The work shall consist of clearing, grubbing and removal of trees, shrubs, brush and other vegetation within the work area, right-of-way and from other areas designated on the plans or by the Engineer.

2.0 PRODUCTS

None in this section

3.0 EXECUTION

3.1 Construction

- 3.1.1 All shrubbery, brush, weeds, other vegetation, downed timber, branches and roots, rubbish and other deleterious material shall be cleared as indicated on the plans or as directed by the Engineer and disposed of at the City of Regina Landfill, unless otherwise approved by the Engineer.
- 3.1.2 No trees shall be cut down or pruned without the expressed permission of the Engineer in writing, and in accordance with the *Regina Urban Forest Management Strategy* (Appendix G) and the *Forestry Bylaw #9607*. It shall be the responsibility of the Contractor to preserve any tree for which the special provisions or plans provide or which the Engineer may direct to be preserved.
- 3.1.3 All trees requiring removal shall be removed to a minimum of 250 mm below grade and the stump removed as directed by the Engineer.
- 3.1.4 The ground shall be restored and levelled as designated on the Plans or by the Engineer.
- 3.1.5 Special care shall be taken during the removal of any stumps or roots system where utilities are likely to be damaged to prevent damage to such utilities.
- 3.1.6 All buildings, fences, trees, curbs or other properties which are not to be removed shall be protected during the process of work.